

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27077-00-00
Spot: NWSENE Sec/Twnshp/Rge: 25-23S-16E
3750 feet from S Section Line, 1050 feet from E Section Line
Lease Name: LEEDY Well #: 21
County: WOODSON Total Vertical Depth: 932 feet

Operator License No.: 30661

Op Name: L & B CRUDE, INC.

Address: 402 W. 7TH STREET
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	

\$ 35.00

Well Type: DH

UIC Docket No:

Date/Time to Plug: 03/19/2007 8:00 AM

Plug Co. License No.: 31519

Plug Co. Name: JACKSON, LELAND DBA LONE JACK OIL CO.

Proposal Rcvd. from: JAY LEEDY

Company: L & B CRUDE, INC.

Phone: (620) 963-7303

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 932'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 932', A 50' CEMENT PLUG AT 540', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 03/19/2007 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

TUBING WAS RAN INTO THE WELL TO 932'. 10 SACKS OF CEMENT WEER PUMPED THROUGH THE TUBING TO 932'. THE PIPE WAS PULLED TO 450' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED AND DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

MAY 16 2007

CPT

CHANUTE, KS

INVOICED

DATE 6-5-07
INV. NO. 2007061832

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN) RECEIVED

KANSAS CORPORATION COMMISSION

MAY 25 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

PA