

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20805-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 32-21S-40W  
1250 feet from S Section Line, 1250 feet from W Section Line  
Lease Name: GOULD Well #: 2-32  
County: HAMILTON Total Vertical Depth: 2950' feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2946	0	WITH 470 SX CMT
SURF	8.625	330		WITH 190 SX CMT

**\$ 95.88**

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/02/2007 2:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: FILL 4 1/2" CASING WITH CMT. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/02/2007 4:00 PM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

PUMP 300# HULLS & 175 SX CMT INSIDE 4 1/2" CASING FROM 2818' TO 0'.  
PRESSURED TO 750# & HELD. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS. ATTEMPT  
TO PUMP. PRESSURE WENT TO 700#. ANNULUS IS FULL.

**Perfs:**


Top	Bot	Thru	Comments
2812	2818		
2800	2806		
2758	2863		

**INVOICED**  
DATE 6-5-07  
INV. NO. 2007061822

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed

*Ken Jehlik*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 25 2007

CONSERVATION DIVISION  
WICHITA, KS

Form C-233

*PKT*