

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20789-00-00  
Spot: SW Sec/Twnshp/Rge: 19-24S-37W  
1320 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: MCCORMICK GU Well #: 2  
County: KEARNY Total Vertical Depth: 3100 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 WEST OKLAHOMA AVENUE  
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3100	0	WITH 610 SX CMT
SURF	8.625	769		WITH 450 SX CMT

\$100.75

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/02/2007 9:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA Phone: (620) 356-6955

**Proposed Plugging Method:** MIX AND PUMP 325 SACKS CEMENT W/ 800LBS OF COTTONSEED HULLS TO FILL THE CASING FROM GROUND LEVEL TO 2900'. CEMENT BLEND TO BE 60/40 POZ W/ 6% GEL MIXED AT 13.1 PPG, YEILD 1.53 CUFT/SK. HAVE 50 EXTRA SACKS OF CEMENT ON LOCATION TO FILL THE ANNULUS BETWEEN THE 8.625" AND 5.5" CASING. CUT OFF AND CAP THE CASINGS 5' BELOW GROUND LEVEL. RESTORE THE LOCATION.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/02/2007 1:00 PM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

PUMP 100 SX CMT WITH 300# HULLS DOWN 5 1/2" CASING. FINISH FILLING 5 1/2" CASING WITH 170 SX CMT. PRESSURE TO 200#. CASING STAYED FULL OF CMT. HOOK UP TO 5 1/2" X 8 5/8" ANNULUS AND PUMPED 10 SX CMT TO FILL. PRESSURE TO 200# & HELD.

**Perfs:**


Top	Bot	Thru	Comments
2806	2900		

**INVOICED**  
DATE 6-5-07  
INV. NO. 2007061823

Remarks: USED CLASS C CMT 2% GEL & 2% CC BY ORR ENTERPRISES.

Plugged through: CSG

District: 01



Signed

*Ken Jehlik*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 25 2007  
CONSERVATION DIVISION  
WICHITA, KS