

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00778-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 17-30S-8W
3713 feet from S Section Line, 5231 feet from E Section Line
Lease Name: HOLCOMB Well #: 1
County: KINGMAN Total Vertical Depth: 4280 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE.
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4273		125 SX
SURF	8.625	257		175 SX

\$ 139.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2007 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50 FEET ABOVE THE PERFS, RECOVER PIPE, 35 SKS 1300', 35 SKS 850. CIRC 310'. PERFS, 4226-30, 4234-38 PBTD 4260.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 04/19/2007 4:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4175, AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 3050 AND PULLED TO 1300', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 310', WHERE CMT WAS CIRC TO SURFACE. REMAINING PIPE PULLED.

Perfs:

Top	Bot	Thru	Comments
4234	4238		
4226	4230		
4210	4220		
4188	4198		

INVOICED
DATE 6-5-07
INV. NO. 2007061824
RECEIVED
KANSAS CORPORATION COMMISSION
MAY 24 2007

Remarks: UNITED CMTG 7779 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS

