

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20538-00-00  
Spot: NENESE Sec/Twnshp/Rge: 7-30S-7W  
2329 feet from S Section Line, 470 feet from E Section Line  
Lease Name: KOHMAN Well #: 4  
County: KINGMAN Total Vertical Depth: 4554 feet

Operator License No.: 8740  
Op Name: BRAMWELL PETROLEUM, INC.  
Address: 15183 SW 25TH AVE.  
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4222		140 SX
SURF	8.625	224		200 SX

\$ 148.01

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: \_\_\_\_\_ Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50 FT ABOVE PERFS CAP WITH 5 SKS OF CMT. PERFS 3793-3796, 4100-04 PBD 4160

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/23/2007 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE CONVERTED WITH SAND TO 3740' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS PULLED FROM 3000' TO 1250', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED, THE CASING WAS PULLED TO 275', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4100	4104		
3793	3796		

INVOICED  
DATE 6-5-07  
INV. NO. 2007061824

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 24 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: UNITED CMT 60/40 4% GEL #7781

Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

[Handwritten mark]

[Handwritten mark]