

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-087-20535-00-01  
Spot: NESESE Sec/Twnshp/Rge: 30-9S-20E  
1085 feet from S Section Line, 227 feet from E Section Line  
Lease Name: MCLOUTH GAS STORAGE FIELD Well #: 0-131  
County: JEFFERSON Total Vertical Depth: 1561 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPEL  
Address: 4700 HIGHWAY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1561		180 SX
SURF	8.625	103		75 SX

**\$ 50.73**

Well Type: GSO UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2006 8:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING & ROUST SVS, INC.  
Proposal Rcvd. from: BERNIE ROCKER Company: SOUTHERN STAR CENTRAL GAS P Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO TOTAL DEPTH. PLUG SOLID WITH CEMENT. CUT CASING 4' BELOW GROUND. BACKFILL AND RECLAIM.

Plugging Proposal Received By: STEVE KORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/03/2006 5:00 PM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

RAN 1" TUBING INSIDE OF 4.5" CASING TO 1525' AND PUMPED CEMENT FROM 1525' TO SURFACE. PULLED THE TUBING AND TOPPED WELL OFF. HOOKED ON TO 4.5" CASING AND SQUEEZED CEMENT. SHUT IN PRESSURE WAS 850 POUNDS. TOTAL CEMENT USED WAS 140 SACKS. CUT THE CASING OFF 5' BELOW SURFACE AND BACKFILLED.

**Perfs:**

Top	Bot	Thru	Comments
1213	1515		

INVOICED

DATE 6-5-07  
INV. NO. 2007061837

RECEIVED  
KCC DISTRICT #3

MAY 18 2007 TCH

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 25 2007

Form CP-2/3

CONSERVATION DIVISION