

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00924-00-01
Spot: SENWSW Sec/Twnshp/Rge: 36-30S-9W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BOHRER Well #: 1
County: KINGMAN Total Vertical Depth: 4490 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4489		200 SX
SURF	10.75	270		250 SX

\$ 145.93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2007 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PERFS 4422'-28', 4438'-46'. SAND BACK 50' ABOVE PERFS, CAP WITH 5 SKS CMT, RECOVER CASING, 35 SKS 1500', 35 SKS 950', CIRC 330-0.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 04/04/2007 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4375' AND CAP WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3050' AND PULLED TO 1500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 320', WHERE CMT WAS CIRC TO SURFACE REMAINING CASING PULLED AND CMT TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4438	4446		
4422	4428		

INVOICED

DATE 6-5-07
INV. NO. 200 7061841

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 24 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED CMT #7683 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)