

3-12
4- 041356

196
K

22812-0000

KCC
ajb
6-7-06

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20-212-00-00

W2 SW SW /4 SEC. 13 , 09 S, 19 W
660 feet from S section line
4950 feet from E section line

Operator license# 6931

Lease Hilgers well # 2

Operator: Bowman Oil Company

County Rooks

Address: Box 17
Codell, Kansas 67630

Well total depth 3539 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 209 feet

11501

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Plainville, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 12 Month: March Year: 92

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone:

Were: 5 1/2" casing set @ 3563'. T.D. 3539'. Perf. @ 3331' - 3534'.
Anhy. - D.V. 1400' w/350 sx. W.L.M. 3460'. Top of fluid @ 2000'.
Order 300 sxs. 60/40 poz. - 10% gel. with 1/4# F.C. plus 600# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 9:30A.M. Day: 12, Month: March, Year: 92

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 245 sx.
60/40 pozmix - 10% gel. with 600# hulls. - 1200# Max. P.S.I.
1000# S.I. Checked 8 5/8" S.P. cement circulated to surface.

Remarks: W.L.M. - 3500'.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING X. Elevation:

I did X did not[] observe the plugging.

Dennis L. Hamel
110 (agent)

STATE CORPORATION COMMISSION
RECEIVED
APR 0 1992
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 4-21-92
INV. NO. 34968
3-12