

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08527-00-00
Spot: SENWNW Sec/Twnshp/Rge: 8-15S-13W
4290 feet from S Section Line, 4470 feet from E Section Line
Lease Name: ANDERSON REIN UNIT Well #: 2
County: RUSSELL Total Vertical Depth: 3263 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	2966	0	150 SX CMT.
SURF	10.75	743	0	325 SX CMT. \$ 106.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2007 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2007 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfed at 1425' and 750'.
Ran tubing to 2500' - pumped 100 sxs 60/40 pozmix - 10% gel cement with 450# hulls.
Pulled to 1400' - pumped 100 sxs cement with 350# hulls.
Pulled to 700' - circulated with 115 sxs cement.
POOH. Tied onto backside - pumped 40 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.
Topped off casing with 45 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2944	3064		LKC

INVOICED
DATE 6-5-07
INV. NO. 2007061834

Remarks: LEASE ORIGINALLY KNOWN AS MARY E. ANDERSON #4. QUALITY CEMENT COMPANY.

Plugged through: TBG

District: 04 RECEIVED
KANSAS CORPORATION COMMISSION

Signed Casa Morris
(TECHNICIAN)

MAY 30 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAY 25 2007

Handwritten signature

SKELLY OIL CO. #4 MARY E ANDERSON 8-15-13W SW SE NW NW


Contr _____ RUSSELL County

E 1771 Comm 2-15-44 Comp 4-5-44 IP 269 BOPD

Tops	Depth	Datum
ANHY	738	
DODGE	2895	
LANS	2942	
TD	3044	

Casing
 10" 743
 6" 2966

Old I P 152 BOPD
 Pay 2966-96
 A/750, 400' OIH/24 hr
 OWDD: 5-18-46
 OTD 2996
 A/2000



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS