

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19170-00-02
Spot: N2S2SW Sec/Twnshp/Rge: 8-15S-13W
990 feet from S Section Line, 3960 feet from E Section Line
Lease Name: J DETRICH Well #: 5
County: RUSSELL Total Vertical Depth: 3176 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3165	0	350 SX
SURF	10.75	406	0	240 SX

\$103.22

Well Type: EOR UIC Docket No: E07553.3 Date/Time to Plug: 04/30/2007 2:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2007 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfed at 1450' and 750'.
Ran tubing to 1500' - pumped 150 sxs 60/40 pozmix - 10% gel cement with 500# hulls - cement circulated.
POOH. Tied onto casing - pumped 50 sxs cement.
Max. P.S.I. 800#. S.I.P 400#.
Pressured 6 5/8" - 5 1/2" annulus to 800# P.S.I.

Perfs:

Top	Bot	Thru	Comments
2935	2948		

INVOICED
DATE 6-5-07
INV. NO. 2007061834

Remarks: QUALITY CEMENT COMPANY.

Plugged through: TBG

District: 04

Signed

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 30 2007

Form CP-2/3

MAY 25 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten signature]

REPLACEMENT CARD

CARTER OIL COMPANY

#5 J. DETRICH 'OWWO'

8-15-13W
C N/2 S/2 SW

CONTR UNKNOWN

CTY RUSSELL


GEOL

FIELD TRAPP

ELV 1747 DF SPD E6/1/58

CARD ISSUED 7/4/58

IP P 209 BOPD, NW
LKC 2972-3142 OA



API NOT ASSIGNED

SMP	Tops	Depth/Datum
<i>Arh</i>		745
TOP		2590- 843
LANS		2897-1150
ARB		3170-1423
PBTD		3156-1409
ORTD		3176-1429

OLD INFO: OPERATOR WAS SAME, WELL NAME SAME, SPD 5/20/37, SET 10" 400+, 6" 3173, COMP AS OIL WELL, ARB OH 3173-3176, 6/20/37, CONTR: UNKNOWN
NO CORES OR TSTS
MICT - CO, (ARB OH), GSO, POP, OIL WELL (POTENTIAL NOT RPTD)

NEW INFO: PROD DECL, REWORKED E 6/1/58, MICT - CO, PB 3165 TD, SET 4" LINER AT 3165, PF (LKC) 16 / 3134-3142, 44 / 3090-3101, 24 / 3071-3078, 12 / 3054-3057, 48 / 2993-3005, 16 / 2982-2986, 24 / 2972-2978, AC 14,000 GAL, GSO, POP, P 209 BOPD, NW

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

INFO RELEASED: 3/5/87 - RE-ISSUED CARD TO CLARIFY INFO.
MAY BE MISSING FROM SOME FILES