

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19171-00-01  
Spot: SWSWSW Sec/Twnshp/Rge: 8-15S-13W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: J DETRICH Well #: 1  
County: RUSSELL Total Vertical Depth: 3211 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3207	0	400 SX
SURF	12.5	327	0	250 SX

# 104.36

Well Type: EOR UIC Docket No: E07553.2 Date/Time to Plug: 04/19/2007 2:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/19/2007 5:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfed at 800' and 1475'.  
Ran tubing to 2950' - pumped 50 sxs 60/40 pozmix - 10% gel cement with 400# hulls.  
Pulled to 2750' - pumped 20 sxs gel.  
Pulled to 1500' - circulated with 180 sxs cement with 300# hulls.  
POOH. Pumped 10 sxs down casing.  
Max. P.S.I. 500#. S.I.P. 400#.  
Pumped 25 sxs down 7" - 10" annulus.  
Max. P.S.I. 200#. S.I.P. 200#.  
Pumped 50 sxs down 10' - 13" annulus.  
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
2927	2992		

INVOICED

DATE 6-5-07  
INV. NO. 2007061834

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

RECEIVED  
KANSAS CORPORATION COMMISSION

Signed

*Case Morris*

(TECHNICIAN)

MAY 30 2007

CONSERVATION DIVISION

Form CP-2/3

MAY 25 2007

*PT*

replacement card

CARTER OIL COMPANY  
DENVER, CO. 80217

8-15 -13W  
SW SW SW

#1 J. DETRICH OWWO

site: 8-1/4 S & 1-3/4 E OF RUSSELL, KS

city: RUSSELL

API IUG-55765

contr: UNKNOWN

field: TRAPP

geol:

fr  
date 09/01/47

spd  
date 01/24/38

drig  
comp

card  
issued 09/01/47

last  
revised 08/05/87


ELV: 1779 DF SMP  
 tops .....depth/datum  
 ANH .....780 +999  
 TOP .....2630 -851  
 RTD OLD .....2888 -1109  
 LANS .....2934 -1155  
 DDTD .....2980 -1201  
 ARB .....3206 -1427  
 DDTD-2 .....3211 -1432

IP status:

OIL, P 1750 BOPD, ARB OH 3207-3211 ,

OLD INFO: OPERATOR WAS CARTER OIL COMPANY, 1  
 J. DETRICH, SPD 11/09/36 , 12" 327, 8" 2732, 6" 2878,  
 OIL, SHAW 2798-2820 , (CARD ISSUED 09/01/47 )  
 CONTR: UNKNOWN

INFO RELEASED: 8/5/87 - REISSUED CARD TO CLARIFY  
INFO

CORE (1) 2740-2743 (TOP), CUT 3', FULL REC - DETAILS NA

NO DSTS

MICT - CO, PF (TOP) 2798-2820, AC 3000 GAL, FLO 47 BOPD, RE-AC 3000 GAL, FLO 80 BOPH,  
POP, P 210 BOPD, 12/14/36

1 WSHDWN:

OPERATOR WAS CARTER OIL COMPANY #1 J. DETRICH OWWO REWORKED 07/31/37 , , OIL,  
LKC OH 2878-2980 , (CARD ISSUED 09/01/47 )

CONTR: UNKNOWN

MICT - CO TO 2898, DD 2980 TD (LKC OH), AC 1000 GAL, GSO, POP, P 1542 BOPD, 7/31/37

NEW INFO: FR 09/01/47 , REWORKED 01/24/38 MICT - CO TO 2980, DD 3211 TD (ARB OH), SO  
FROM 3207- 3211, SET 5" LINER TO 3207, GSO, NAT, POP, P 1750 BOPD, 1/28/38