

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-19010-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 13-31S-9W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: GRABS Well #: A-2
County: HARPER Total Vertical Depth: 4422 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4411		100 SX CMT.
SURF	8.625	262		200 SX CMT.

\$ 143.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2007 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: -98.24760, 37.34883 SAND BACK 50 FT ABOVE PERFS CAP WITH 5 SKS OF CMT. RECOVER CASING 35 SKS 1425.35 SKS 950', CIRC 315-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/26/2007 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND FROM 4420' TO 4360' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3060' AND PULLED TO 1425', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 950' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 315', WHERE CMT WAS CIRC TO SURFACE REMAINING CASING PULLED AND CMT TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4411	4422		

INVOICED
DATE 6-5-07
INV. NO. 2007061836

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: UNITED CMTG 60/40 4% GEL

MAY 24 2007

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed _____

(TECHNICIAN)