

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22048-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 22-30S-9W  
1650 feet from N Section Line, 330 feet from W Section Line  
Lease Name: SWINGLE A Well #: 1  
County: KINGMAN Total Vertical Depth: 4450 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 904 N. LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4447	<u>3100</u>	25/125 SX CMT.
SURF	8.625	266		265 SX CMT.

\$ 144.63

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/12/2007 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS CAP WITH 5 SKS OF CMT. RECOVER CASING. 35 SKS 1500, 35 SKS. PERFS 4284-4326

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/12/2007 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4230' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3100', AND PULLED TO 1500' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 315', WHERE CMT WAS CIRC TO SURFACE. REMAINING CASING WAS PULLED AND THE CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4284	4326		

**INVOICED**  
DATE 6-5-07  
INV. NO. 2007061836

RECEIVED  
KANSAS CORPORATION COMMISSION  
**MAY 24 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CMTG 60/40 4% GEL -98.29882, 37.42310 #7778

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)