

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00610-00-00
Spot: NENENW Sec/Twnshp/Rge: 32-5S-20W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RAY B Well #: 1
County: PHILLIPS Total Vertical Depth: 3601 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3591	0	w/unknown sxs cmt
SURF	10.75	135	0	w/unknown sxs cmt

#117.03
~~\$39.75~~

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2007 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GEORGE STOPPELWERTH Company: DARRAH, JOHN JAY, JR. Phone: (316) 263-2243

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 800# hulls.
Fluid level 960'. PBSD 3495'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2007 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 1100' and 1725'.
Swift Services pumped 50 sxs 60/40 pozmix - 10% gel neat - followed with 200 sxs with 500# hulls.
Max. P.S.I. 500#. S.I.P. 150#.
Displaced to 160'. Perforated 3 holes at 160'.
Swift pumped 100 sxs with 100# hulls - circulated cement out 10 3/4" surface pipe.

Perfs:

Top	Bot	Thru	Comments
3572	3591	OH	Completion

INVOICED

DATE 6-6-07

INV. NO. 2007061852

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 01 2007

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Richard Williams

(TECHNICIAN)

Form CP-2/3

MAY 24 2007

Barnett Drlg. Inc.

1 " B Ray

32-5-20W
NE NE NW

Contr.

Phillips


County

E 2188 Comm. 8-13-41 Comp. 9-10-41 IP Max-3000

Topo	Depth	Datum
ANHY	1710	
BEAG	3591	
T.D.	3601	

Casing
10" 135
5" 3591

At 3601, 2750' OIR



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS