

State Conservation Commission  
200 Colorado Derby Building  
Wichita, Kansas 67202

15-065-02811-00 -0002  
KCC afB

API Number Drd1 1957  
LEASE NAME Brush Creek Unit 5-29-07  
WELL NUMBER 304  
2970 330 Ft. From S. Section Line  
1980 3630 Ft From E. Section Line  
SEC 9 TWP. 9 RNG 23W  
COUNTY Graham  
Date Well Completed  
10/11/57  
Plugging Commenced  
.07/31/06.....  
Plugging Completed  
7/31/06

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days

OPERATOR: John J. Darrah, Jr.  
ADDRESS: 225 N. Market, #300, Wichita, KS 67220  
PHONE# (316) 262243 OPERATORS LICENSE NO: 5088~  
Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

KCC 8/19/06  
PRT  
per oper.  
George  
Stoepelwerth

The plugging proposal was approved on 7/24/06

by Herb Deines

KCC District Agent's Name

Is ACO-1 Filed? \_\_\_\_\_ If not, is well log attached? filed w/ Plug App

Producing formation Lansing Death to Top 3733 Bottom 3890 T.D. 3910

Show depth and thickness to all water, oil and gas formations

OIL, GAS OR WATER RECORDS		I		CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled OUT
<u>Lansing</u>	<u>Oil &amp; Water</u>	<u>3733</u>	<u>3890</u>	<u>8 5/8</u>	<u>223</u>	<u>0</u>
				<u>5 1/2</u>	<u>3910</u>	<u>0</u>

RECEIVED  
AUG 08 2006  
KCC WICHITA

CIBP 3666

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, if cement or other plugs were used, state the character of same and depth placed, from \_\_\_ ft to \_\_\_ feet each set.

CIBP @ 3666, Top of casing leak at 1750. Tubing to 3700 mixed 8 sx gel and 10 sx 60-40 poz, tubing to 2100', pumped 7 sx gel, tubing to 1750, pumped 250 sx 60-40 and 10 sx gel, lost circ at end of mixing, tubing to 750', pump 125 sx & circ to surface. Pulled tubing, 25 sx squeezed from top to 400 psi.

Name of plugging contractor Copeland Acid and Cement License No. 33555  
Address PO Box 438, Haysville, KS 67060  
Name of plugging contractor Kcwell service, Inc

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah, Jr.

STATE OF Kansas COUNTY OF Sedgwick, ss.


G>P> Stoepelwerth, Agent of above-described well, first being duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

*[Handwritten Signature]*

225 N. Market #300, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 8th day of August, 2006



*[Handwritten Signature]* Notary Public

My Commission Expires: 9/1/2006

PRT