

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: John O. Farmer, Inc.
 Address: P.O. Box 352, Russell, KS 67665
 Phone: (785) 483-3144 Operator License #: 5135
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: District #4 (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3771' Bottom: 3778' T.D. 3778'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 137-00,507 -00 -00
 Lease Name: Fought
 Well Number: #3
 Spot Location (QQQQ): _____ - SW - SW - SE
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
 Sec. 25 Twp. 3 S. R. 24 East West
 County: Norton
 Date Well Completed: Feb. 1954
 Plugging Commenced: 2:30 P.M., 4-5-07
 Plugging Completed: 3:30 P.M., 4-5-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil & water	3771'	3778'	8-5/8"	260'	-0-
				5-1/2"	3771'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Tubing @ 2500'; mixed 100 sks. cement w/200# hulls. Tubing @ 1200'; mixed 85 sks. cement w/300# hulls. Hooked on to 5-1/2" casing. Mixed 25 sks. cement - maximum 500 PSI pressure. Shut in @ 500 PSI. Hooked on backside. Mixed 50 sks. cement - maximum pressure 150 PSI. Shut in @ 100 PSI.

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: _____
 Address: P.O. Box 31, Russell, KS 67665
 Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.
 State of Kansas County, Russell, ss. _____
John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

99996
 RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 22 2007
 CONSERVATION DIVISION
 WICHITA, KS

(Signature) John O. Farmer III
 (Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 21st day of May, 20 07
Margaret A. Schulte My Commission Expires: _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

W.R. 1091
T3

COMPANY: Wood River Oil & Refining Co., Inc.
 CONTRACTOR: Empire Drilling Company
 FARM: Cora Fought #3
 LOCATION: (SW SW SE) C S $\frac{1}{2}$ S $\frac{1}{2}$, Sec. 25-3-24
 Norton County, Kansas
 COMMENCED: 2-4-54
 COMPLETED: 2-13-54

COPY

0	to	273	Surface Hole
273	to	2038	Shale and shells
2038	to	2070	Anhydrite
2070	to	2970	Shale and shells
2970	to	3040	Shale and lime
3040	to	3125	Shale and shells
3125	to	3245	Shale and lime
3245	to	3330	Lime and shale
3330	to	3420	Shale and lime
3420	to	3675	Lime
3675	to	3773	Lime and shale
3773			R.T.D. drilled deeper

Set 260' of 8-5/8" Surface Casing, cemented with 135 sacks of cement.

ELEVATION: 2454 D.F.

TOPS: Heebner 3477'; L.S. K.C. 3517'; Arbuckle 3767'; R.T.D. 3773'.

Set at 3771' - 5 1/2" Casing, cemented with 150 sacks of cement.

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log of the Cora Fought #3, C S $\frac{1}{2}$ S $\frac{1}{2}$, Section 25, Township 3, Range 24 West, Norton County, Kansas, as reflected by the files of the Empire Drilling Company.

Dan J. Kornfeld
Dan J. Kornfeld

Subscribed and sworn to before me a Notary Public within and for Sedgwick County, Kansas, this 17th day of February 1954.

Maryl Weimer
NOTARY PUBLIC

My Commission Expires May 5, 1956

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 22 2007

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

25214

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

COPY

DATE <u>4-5-07</u>	SEC <u>25</u>	TWP <u>35</u>	RANGE <u>24W</u>	CALLED OUT	ON LOCATION <u>12:45 PM</u>	JOB START <u>2:30 PM</u>	JOB FINISH <u>3:30 PM</u>
LEASE <u>Fought</u>	WELL # <u>3</u>	LOCATION <u>NORTON 6S-4W-1N-1/2W-S</u>			COUNTY <u>NORTON</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR POE SERVICES
 TYPE OF JOB OLD HOLE
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2" DEPTH _____
 TUBING SIZE 2 7/8" DEPTH 2500'
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER SAME

CEMENT
 AMOUNT ORDERED 375 SKS 60/40 P&Z 1066EL
500# Hulls
Used 260 SKS 60/40 P&Z 1066EL 500# Hulls

COMMON	<u>156 SKS</u>	@ <u>12.60</u>	<u>1965.60</u>
POZMIX	<u>104 SKS</u>	@ <u>6.40</u>	<u>665.60</u>
GEL	<u>22 SKS</u>	@ <u>16.60</u>	<u>366.30</u>
CHLORIDE	_____	@ _____	_____
ASC	_____	@ _____	_____
	<u>Hulls 500#</u>	@ <u>25.30</u>	<u>127.30</u>
	_____	@ _____	_____
	_____	@ _____	_____
	_____	@ _____	_____
	_____	@ _____	_____
	_____	@ _____	_____
HANDLING	<u>412 SKS</u>	@ <u>1.90</u>	<u>782.80</u>
MILEAGE	<u>94 PER SKI mile</u>	@ _____	<u>3411.36</u>
TOTAL			<u>7319.96</u>

REMARKS:

TUBING AT 2500' max 100 SKS
Cement with 200# Hulls
TUBING AT 1200' max 85 SKS
Cement with 300# Hulls. Hook on
TO 5/8 CASING. MIX 25 SKS CEMENT MAX 500 PSI
PRESSURE SHUT IN AT 500 PSI. Hook
ON BACKSIDE MIX 50 SKS CEMENT, MAX
PRESSURE 150 PSI. SHUT IN 100 PSI.
THANK YOU

SERVICE

DEPTH OF JOB 2500'
 PUMP TRUCK CHARGE 955.00
 EXTRA FOOTAGE @ _____
 MILEAGE 92 ME @ 6.00 552.00
 MANIFOLD @ _____
 @ _____
 @ _____
 TOTAL 1507.00

CHARGE TO: JOHN O. FARMER
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

 @ _____
 @ _____
 @ _____
 @ _____
 @ _____

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 22 2007

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL CONSERVATION DIVISION
 WICHITA, KS

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____