

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Carmen Schmitt Inc.
Address: PO Box 47
Phone: (620) 793-5100 Operator License #: 6569
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/8/07 (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 3995 Bottom: 4028 T.D. 4030
Lansing Depth to Top: 3612 Bottom: 3842 T.D. _____
Plattsmouth / Topeka Depth to Top: 3515 / 3379 Bottom: 3537 / 3474 T.D. _____

API Number: 15-195-00848-00-00
Lease Name: Ogallah Unit
Well Number: 6-3
Spot Location (QQQQ): _____ - sw - ne - se
1650 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 26 Twp. 12 S. R. 22s East West
County: Trego
Date Well Completed: November 1951
Plugging Commenced: 5/8/07
Plugging Completed: 5/8/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	514	8 5/8"	514'	0
		0	4030	5 1/2"	4030'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU DS&W Well Service. Ran in with

133 jts 2 3/8" tubing to 3900'. Riggged up Copeland Cementing and pumped 110 sks cement and 150# hulls. Pulled 40 jts tbg.

Pumped 110 sks and 150#. Pulled 44 jts tbg. Pumped 10 sks, circulated to surface. Pulled tbg, swedged csg, pressured up to 300#. Plugged surface casing with 90 sacks.

Name of Plugging Contractor: DS&W Well Servicing, Inc. License #: 6901


Address: PO Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.

State of Kansas County, Barton, ss.

Jacob L. Porter

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L. Porter

(Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 16th day of May, 20 07

Elaine Meyer My Commission Expires: 12-13-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 17 2007
CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]