

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BEREDCO, INC.
Address: PO BOX 723 HAYS, KS 67601
Phone: (785) 628-6101 Operator License #: 5147
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-11-07 (Date)
by: MARVIN MILLS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
PLATT Depth to Top: 2918 Bottom: 2934 T.D. _____
LKC Depth to Top: 3028 Bottom: 3125 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-06878-00-00
Lease Name: HORACE FINK
Well Number: 2
Spot Location (QQQQ): NW - SW - _____
2092 Feet from North / South Section Line
4630 Feet from East / West Section Line
Sec. 15 Twp. 14 S. R. 14 East West
County: RUSSELL
Date Well Completed: 11-2-43
Plugging Commenced: 5-10-07
Plugging Completed: 5-11-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
PLATT	OIL	0	180	10 3/4	11-2-43	---
LKC	OIL	0	3024	7	11-2-43	----
		2996	3122	5 1/2	11-2-43	---

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


RIG UP MOVE IN WORK STRING WELD COLLAR IN 10 3/4. RUN OPEN ENDED TBG TAG AT 2949. RIG UP ALLIED CEMENTING 2949 SPOT 125 SKS 60/40 POS 10% GEL W/ 500# HULLS. 1808 SPOT 100 SKS 60/40 POS 10% GEL 887 MIX 110 SKS 60/40 POS 10% GEL 100# HULLS CIRC CMT TO SURFACE. PULL TBG HOOK TO 7" MIX 80 SKS 60/40 POS 10% GEL MAX PRESSURE 300# SHUT IN PRESSURE 200# PRESSURE 200# SHUT IN PRESSURE 200# HOOK TO 10 3/4 MIX 60SKS 60/40 POS 10% GEL AT 100# POOR BOY BLEW OUT.

Name of Plugging Contractor: STEWART WELL SERVICE Beredco, Inc License #: 5147 4604 RECEIVED 5/31/07
Address: 1409 WASHINGTON CIRCLE HAYS, KS 67601 KANSAS CORPORATION COMMISSION
Name of Party Responsible for Plugging Fees: ROBERT GRANT W/ BEREXCO, INC. 5363 MAY 21 2007
State of KS County, ELLIS, ss. CONSERVATION DIVISION WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Robert Grant

(Address) PO BOX 723 HAYS, KS 67601



SUBSCRIBED and SWORN TO before me this 16 day of MAY, 20 07.
Shanna Miller My Commission Expires: 9/19/09
Notary Public