

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Wilson C

WELL NUMBER 4

2970 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 35 TWP. 9S RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 3-13-54

Plugging Commenced 1-23-92

Plugging Completed 1-23-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Marion Schmidt (KCC District Agent's Name).

Is AC0-1 filed? On old form If not, is well log attached? -

Producing Formation Lansing Depth to Top 3500 Bottom 3548 T.D. 3863

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| Lansing | Oil | 3500 | 3548 | 8 5/8 | 214 | -0- |
| | | | | 5 1/2 | 3740 | -0- |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 275 sxs 60/40 poz w/8% gel + 500# hulls from 3575' (PBSD) to surface. Pumped 125 sxs cmt down annulus. Job Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

RECEIVED
STATE CORPORATION COMMISSION
2-5-92
FEB 03 1992
CONSERVATION DIVISION
WICHITA, KANSAS

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 92

Andre Thurdock
Notary Public

My Commission Expires: 12-23-93

15-163-00653-00-00

KANSAS GEOLOGICAL SOCIETY
 KANSAS LOG BUREAU - KANSAS WELL SAMPLING BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Francis Oil & Gas, Inc.

SEC. 35 T. 9 R. 20W
 LOC. SW SE NE

FARM Wilson C

NO. 4

RECEIVED
 STATE CORPORATION COMMISSION

OCT 14 1991

COUNTY Rooks

TOTAL DEPTH 3863'

COMM. 2/18/54

COMP. 3/7/54


CORPORATION DIVISION
 Wichita, Kansas

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

| | | |
|----|----|-------|
| 20 | 10 | |
| 15 | 8 | 214' |
| 12 | 6 | |
| 13 | 5 | 3740' |

ELEVATION 2253 K.B.


PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|--------------------------|------|
| Surface Sand & Gravel | 125 |
| Shale & Sand | 214 |
| Shale | 750 |
| Shale & Sand | 835 |
| Shale & Red Bed Streaked | 980 |
| Sand, Shale & Shells | 1120 |
| Shale & Shells | 1205 |
| Sand & Shale | 1430 |
| Shale | 1680 |
| Shale & Red Bed | 1710 |
| Anhydrite | 1745 |
| Shale, Red Bed & Shells | 1980 |
| Shale & Shells | 2045 |
| Shale, Shells & Salt | 2145 |
| Shale & Lime Shells | 2300 |
| Shale & Lime | 3448 |
| Lime & Shale Broken | 3497 |
| Lime | 3564 |
| Lime & Shale | 3760 |
| Chert, Lime & Shale | 3776 |
| Conglomerate | 3825 |
| Chert & Lime | 3863 |

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.


By 

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 10th day of March, 1954.


 Notary Public

My Commission expires February 13, 1956.