

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 35 Twp. 9 Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines SE NW SE/4

Lease Owner Francis Oil & Gas, Inc.

Lease Name Wilson C Well No. 6

Office Address 905 Palace Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed June 16, 1954

Application for plugging filed June 16, 1954

Application for plugging approved June 16, 1954

Plugging commenced June 16, 1954

Plugging completed June 16, 1954

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3875 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	226	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy Rotary Mud to 210' - set
plug and 1/2 sack hulls and 15 sacks cement through
drill pipe. Mudded hole to 40 ft. set plug and 1/2
sack hulls and 10 sacks cement at the surface.


Name of Plugging Contractor H-30, Inc.
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1954

My commission expires February 13, 1956. Notary Public.



15-163-02453-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Francis Oil & Gas, Inc.**


SEC. **35** T. **9S** R. **20W**
 LOC. **SE 34 SE**

FARM **Wilson C** NO. **6**

TOTAL DEPTH **3875'**
 COMM. **6/1/56** COMP. **6/17/56**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Rooks**

KANSAS



CASING
 20 10
 15 8 **225'**
 12 6
 13 5

ELEVATION **2250 L.S.**

PRODUCTION **Oil**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & sand	110
Sand & Shale	156
Shale	780
Sand	815
Shale with streaks of Sand	1160
Sand	1344
Sand & Shale	1410
Red Bed	1590
Shale & Red Bed	1695
Anhydrite	1780
Shale & Shells	2030
Shale, Shells & Salt with Lime Streaks	2195
Shale & Lime - broken	2313
Shale & Lime	2502
Shale & Lime with Iron Streaks	2532
Lime	2635
Shale & Lime	2818
Chert	3052
Cherty Lime & Shale	3875

FORMATION TOPS (K.S. Meas.)

NEEDLE	3170
TORONTO	3190
LANSING	3510
BARNHART	3729
CONGLOMERATE	3770
ANDRICKLE	3865

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

RECORDED
 STATE OF KANSAS

BY *C. R. Spangenberg*

STATE OF KANSAS
 COUNTY OF **ANDRICKLE** SS:

CONCERNING

Subscribed and sworn to before me, a notary public, in and for said County and State this 21st day of June, 1956.

Paul Lusey

My Commission expires February 11, 1956.

PLUGGING
 FILE SEC. **35** T. **9** R. **20W**
 BOOK PAGE **41** LINE **38**