

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 7 Twp. 9 Rge. 21 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE SE SW

Lease Owner C-G Drilling Co.

Lease Name Cooley Well No. 2

Office Address 107 Rule Bldg., 321 E. William, Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-20 1954

Application for plugging filed 3-19 1954

Application for plugging approved 3-19 1954


Plugging commenced 3-20 1954

Plugging completed 3-20 1954

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production -- 19---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3878 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|---------|------------|
| | | | | 8-5/8" | 174.01' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 170'; set plug; 1/2 sack hulls, 15 sacks cement. Filled hole with mud to 40'; set plug then filled to top with 10 sacks cement 1/2 sack hulls

REC'D
STATE CORP COM
3/24/54

CONSERV DIV
Wichita

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO.
Address 107 Rule Building, 321 East William, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Vicky Jacobs (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vicky Jacobs
Office Manager
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1954

Barbara Donaldson
Notary Public.

My commission expires June 17, 1957

PLUGGING
FILE REC 7 7 9 2/10
BOOK PAGE 22 LINE 21

CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. FARM NAME COOLEY WELL #2
 LOCATION NE SE SW, Sec. 7-9-21W
 POOL NAME Morel COUNTY Graham STATE Kansas
 COMMENCEMENT DATE March 12, 1954 COMPLETION DATE March 20, 1954

LOG OF WELL

Elevation: 2291 R.B.
 All measurements from the top of rotary bushing.

| FROM | TO | FORMATION | DEVIATION FROM VERTICAL | REMARKS: |
|------|------|--------------|-------------------------|----------|
| 0 | 174 | Shale | | |
| 174 | 600 | Shale | | |
| 600 | 1110 | Shale-Sand | | |
| 1110 | 1210 | Sand | | |
| 1210 | 1325 | Shale | | |
| 1325 | 1525 | Sand | 0° - 1500' | |
| 1525 | 1600 | Red Bed | | |
| 1600 | 1784 | Red Bed | | |
| 1784 | 1822 | Anhydrite | | |
| 1822 | 2160 | Shale-Shells | 0° - 2000' | |
| 2160 | 2350 | Shale | | |
| 2350 | 2505 | Lime-Shale | 0° - 2500' | |
| 2505 | 2650 | Shale-Lime | | |
| 2650 | 2790 | Lime-Shale | | |
| 2790 | 2895 | Lime-Shale | | |
| 2895 | 3050 | Shale-Lime | 0° - 3000' | |
| 3050 | 3210 | Lime-Shale | | |
| 3210 | 3320 | Lime-Shale | | |
| 3320 | 3400 | Shale-Lime | | |
| 3400 | 3500 | Lime-Shale | 0° - 3500' | |
| 3500 | 3555 | Lime-Shale | | |
| 3555 | 3620 | Lime-Shale | | |
| 3620 | 3670 | Lime-Shale | | |
| 3670 | 3715 | Lime-Shale | | |
| 3715 | 3800 | Lime-Shale | | |
| 3800 | 3839 | Shale-Lime | | |
| 3839 | 3878 | Lime-Shale | | |

CASING LEFT IN HOLE AFTER COMPLETION

Ran 174.01' (6 jts) of 8-5/8" Surface Casing.
~~Ran no OD casing.~~

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Vicky Jacobs
 Office Manager

Subscribed and sworn to before me this 22nd day of March, 1954.

My commission expires: June 17, 1957

Barbara Donaldson
 Notary Public

