

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS County. Sec. 22 Twp. 9 Rge. (E) 19 (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines SW SW NW

Lease Owner GRAMEHART-MILLER OIL COMPANY

Lease Name BARTOS "B" Well No. 1

Office Address 1005 EAST SECOND STREET

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed APRIL 10 1954

Application for plugging filed APRIL 10 (verbal) 1954

Application for plugging approved APRIL 10 (verbal) 1954

Plugging commenced APRIL 10 1954

Plugging completed APRIL 10 1954

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production ----- 19---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ELDON PETTY BOX 326 HAYS, KANSAS

Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 3645 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	180'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED HOLE WITH MUD TO 175'  
SET BOTTOM PLUG WITH 1/2 SACK  
HULLS AND 15 SACKS CEMENT.  
FILLED HOLE WITH MUD TO 40',  
SET TOP PLUG WITH 1/2 SACK HULLS,  
AND 10 SACKS CEMENT. MUD TO  
SURFACE....

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
APR 14 1954

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor GRAHAM-MESSMAN-RINEHART DRILLING COMPANY  
Address 1003 EAST SECOND STREET WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
J. A. GILLILAND (employee of owner) or NOTARY PUBLIC of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
1005 EAST SECOND STREET WICHITA, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of April, 1954  
Betty June Bayles  
Notary Public.

My commission expires SEPTEMBER 11, 1957.

PLUGGING  
FILE SEC 22 T 9 R 196  
BOOK PAGE 26 LINE 20

DARTON NO. 1 "H"

WELL RECORD

Location: SW 34 NW 22-9-19W  
Rooks County, Kansas

Commenced: March 31, 1954

Operator: Granhart-Miller Oil Company  
1005 S. 2nd Wichita, Kansas

Completed: April 10, 1954

Elevation: 2145 R.S.

Contractor: Graham-Messner-Granhart Drig. Co.  
1005 S. 2nd Wichita, Kansas

Production: O & A

Casing Record: 8 5/8" @ 150' w/115 sacks cement

L O G

Clay	90
Shale & shells	180
Shale & shells	630
Sand	662
Shale & sand	785
Shale & sand	990
Sand	1250
Shale & shells	1500
Shale & shells	1520
Anhydrite	1559
Shale	1630
Shale	1993
Shale & shells	2065
Lime & shale	2225
Lime & shale	2420
Lime & shale	2550
Lime & shale	2700
Lime & shale	2768
Lime & shale	2955
Lime & shale	3110
Lime & shale	3200
Lime	3280
Lime & shale	3310
Lime & shale	3346
Lime	3352
Lime	3362
Lime	3405
Lime	3452
Lime	3472
Lime	3495
Lime	3510
Lime	3587
Conglomerate	3610
Arbuckle	3645 R.T.D.

TOPS

Anhydrite	1520' (-625)
Fopaka	3096' (-951)
Heobner	3300' (-1155)
Toronto	3331' (-1176)
Lansing	3340' (-1195)
Base R.O.	3545' (-1400)
Cherty Conglomerate	3582' (-1437)
Arbuckle	3610' (-1465)

The undersigned, GRAHAM-MESSNER-GRANHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSNER-GRANHART DRILLING COMPANY

By J. A. Gilliland  
J. A. Gilliland  
STATE NOTARY COMMISSION

Subscribed and sworn to before me this 13 day of April, 1954.

Betty Jean Boyler  
Notary Public

APR 12 1954

CONSERVATION DIVISION  
Wichita, Kansas

My commission expires September 14, 1957

