


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rooks County. Sec. 22 Twp. 9 Rge. 19W (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE NE  
Lease Owner Bennett & Roberts Drilling Co.  
Lease Name Bartos Well No. 1  
Office Address Russell, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 7/10 1954  
Application for plugging filed 7/10 verbally 1954  
Application for plugging approved 7/10 verbally 1954  
Plugging commenced 7/10 1954  
Plugging completed 7/10 1954  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3656 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	223'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/heavy mud to 210'. Set plug and mixed 1/2 sack hulls and 15 sacks cement. Filled hole to 40' and cemented with 1/2 sack hulls and 10 sacks cement.

7-16-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst  
Russell, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1954

Clara Hummel

Notary Public.

My commission expires 6/17/54

BOOK PAGE 49 LINE 11  
SEC 22 Twp 9 Rge 19W

Bennett & Roberts Drilling Co.  
Bartos #1

NW NE NE Sec. 22-9-19W  
Rooks County, Kansas

R.T.D. 3656<sup>+</sup>

Comm: 7/1/54  
Comp: 7/10/54

Set 8 5/8" Csg. @ 223<sup>+</sup> w/135 sx amt.

	Tops
Sim. Anhyd.	1545- 621
Topeka Lime	3117- 951
Heebner Shale	3328-1162
Toronto Lime	3343-1177
Lansing K.C.	3364-1198
Gonglomerate	3585-1419
Weathered Arb.	3618-1452
Arbuckle Dolo.	3637-1471

Formation:	Depth:
Surface Clay & Sand	10 <sup>+</sup>
Sand	160
Shale & Sand	180
Blue Shale	600
Shale & Sand	640
Shale	890
Shale & Shells	1030
Sand	1280
Shale	1545
Anhydrite	1572
Shale	1705
Shale, Shells & Red Bed	2040
Lime & shale	2440
Lime	2740
Lime & Shale	3179
Lime	3296
Lime & Shale	3358
Lime	3609
Conglomerate	3637
Arubckle	3656

STATE OF KANSAS)  
RUSSELL COUNTY ) SS.

I hereby certify that the above information is true and  
correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

*Doris Lake*

Subscribed and sworn to before me this 15th day of July, 1954.

*Clara Hummel*  
Notary Public

My Commission Expires 6/17/58

STATE OF KANSAS  
JUL 15 1954  
CONSERVATION COMMISSION  
Wichita, Kansas

PLUGGING  
FILE SEC 22 T 9 R 19W  
BOOK PAGE 49 LINE 11