


## STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

15-163-02965-00-01

NORTH



Locate well correctly on above  
Section Plat

Rooks County, Sec. 22 Twp. 9S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE SE

Lease Owner Sterling Drilling Company, et al

Lease Name Bartos 11B1 Well No. SWDW

Office Address Box 127, Sterling, Kansas

Character of Well (complete Oil, Gas or Dry Hole) Salt Water Disposal

Date well completed 4-22-57 19

Application for plugging filed 4-18-63 19

Application for plugging approved 4-19-63 19

Plugging commenced 5-2-63 19

Plugging completed 5-2-63 19

Reason for abandonment of well or producing formation junk tubing in hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3922' Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3692'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated hole with heavy mud through 2" tubing at 515', 10 sacks cement through tubing at 515', heavy mud up to 250', 10 sacks cement through tubing at 250', heavy mud up to 40', 5 sacks cement through tubing to 0'

Plugging complete at 11 A. M. 5-2-63

RECEIVED  
STATE CORPORATION COMMISSION

MAY 8 1963

5-8-63  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Used Halliburton pump truck

Address

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

F. A. Wuellner

May 4, 1963  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 1963

My Commission Expires Jan. 22, 1966

My Commission Expires BERNARD LAUDERMILK

Bernard Laudermilk

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. R. P. NIXON  
Farm. Bartos "B"

No. 2

SEC. 22 T. 9  
SE NE SE

R. 19W

Total Depth. 3630'

Comm. 2-15-56

Comp. 2-23-56


Shot or Treated.

Contractor. Sterling Drilling Company

Issued. 2-16-57

County Rooks

KANSAS



Elevation. 2170' RB

Production. Dry

CASING:

8 5/8" @236' w/135 sx cem.

Figures indicate Bottom of Formations.

sand & shale	210
shale	975
sand & shale	1220
shale	1510
Anhydrite	1550
shale	1990
shale & lime	2115
shale, sholls	2295
shale & lime	2720
lime	2805
shale & lime	2950
shale	3150
shale & lime	3240
lime	3583
Conglomerate	3630
Total Depth	

Drilled Deeper:

Reworked Arbuckle	3645
Arbuckle	3922
Total depth	

TOPS SCOUT	
Heebner	3324
Lansing	3362
Base/Kansas	
City	3584
Cherty	
Conglomerate	3603

Set 5-1/2" casing at 3692' with 100 sacks cement.  
Stage collar set at 1526' and 300 sacks cement through collar.

RECEIVED  
DIVISION OF SOIL CONSERVATION

APR 19 1963

CONSERVATION DIVISION  
WICHITA, KANSAS