

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,856-00-00

LEASE NAME Bartos

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3960 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 22 TWP. 9S RGE. 19W (E) or (W)

COUNTY Rooks

Date Well Completed 1-21-86

Plugging Commenced 2-8-96

Plugging Completed 2-8-96

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th Street

PHONE# (316) 283-0232 OPERATORS LICENSE NO. 30742

Character of Well SWDW

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 8, 1996 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom T.D. 3890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	3802-3822			8-5/8"	935'	none
	(Inj. Zone)			5-1/2"	3888'	none

RECEIVED
KANSAS CORP COM
FEB 28 1996
A 10:50

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Jet perforated for plugging at 1550' & 950'. Cemented with 100 sacks of Standard and 200 sacks of 40/60 Pozmix, 8% gel. Pumped 100 sacks Standard Cement w/3% cc, 1/4# flocele per sack. Circulated. Cemented to surface on 5-1/2" casing thru Braden Head. Pull tubing from hole & fill casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. Not Required

Address P. O. Box 951046, Dallas, Texas 75395-1046

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Harvey, ss.

Klee R. Watchous (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Klee R. Watchous

(Address) 4924 SE 84th Street, Newton KS 67114-

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 96

Holly L Phares
Notary Public



My Commission Expires: 10-10-99