

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging off formations.

Graham County. Sec. 13 Twp. 9 Rge. (E) 21 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. W $\frac{1}{2}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner. Harbar Drilling Co.
Lease Name. Brault Well No. 2
Office Address. 1019 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Rotary dry hole
Date well completed. 10-22-48 19____
Application for plugging filed. 10-22-48 19____
Application for plugging approved. 10-22-48 19____
Plugging commenced. 10-23-48 19____
Plugging completed. 10-23-48 19____
Reason for abandonment of well or producing formation. no production
If a producing well is abandoned, date of last production. _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well. Merle Rives
Producing formation. _____ Depth to top. _____ Bottom. _____ Total Depth of Well. 3775 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sand, soil & gravel	Fresh water	0	70'	10 3/4	92'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from T.D. (3775') back to 150 ft. from top of hole, where a wooden plug was set and 20 sacks of cement was dumped on top same after which hole was filled with mud on top cement to within 30 ft. of top and another plug was set and 15 sx cement was dumped on top same filling casing to bottom of cellar and bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Harbar Drilling Co.
Address. 1019 Central Bldg., Wichita,


STATE OF Kansas, COUNTY OF Barton, ss.
I, Don S. Packer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn-on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1019 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 48.

My commission expires March 22, 1952

Notary Public.



BRAULT #2

W¹/₂ SW¹/₄ SW¹/₄ Sec. 13--9S--21W, Graham County, Kansas

Rigging up Rotary Tools	9-9-48	Run 3 Jts 10 3/4" surface pipe - Set @
Tearing down Rotary Tools	9-23-48	92 ft. and cemented with 50 sx cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale and clay	0	92
Shale and shells	92	600
Shale and sand	600	880
Sand	880	970
Sand and shale	970	1120
Shale	1120	1235
Sand	1235	1400
Shale	1400	1530
Shale, redbed	1530	1590
Anhydrite	1590	1830
Salt and shale and redbed	1830	2000
Shale	2000	2310
Shale and shells	2310	2390
Lime and shale	2390	2635
Shale	2635	2705
Shale and lime	2705	3500
Lime	3500	3571
Lime and shale	3571	3675
Conglomerated shale	3675	3720
Shale - dry	3720	3745
Lime	3745	3775 Total Depth

I, Don S. Packer, hereby certify that the above log is true and correct to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 15th day of October, 1948

Helen Kelly
Notary Public

My commission expires March 22, 1952

