

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-065-00225-00-00

API NUMBER N/A  
LEASE NAME Balthazor  
WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely and  
return to Cons. Div. office  
within 30 days.

2310 Ft. from S. Section Line  
2310 Ft. from E. Section Line  
SEC. 13 TWP. 9 RGE. 21(E) or (W)  
COUNTY Graham  
Date Well Complete 12-12-49  
Plugging Commenced 11-08-93  
Plugging Completed 11-08-93

LEASE OPERATOR Hallwood Petroleum, Inc.  
ADDRESS 4582 South Ulster Street Parkway, Suite 1700, Denver, CO 80237  
PHONE # (303) 850-6257 OPERATOR LICENSE NO. 3613

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on 11-08-93 (date)  
by Dennis Hamel District 4 (KCC District Agent's Name).  
Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3420 Bottom 3603 T.D. 3733'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	356'	8 5/8	356'	None
		0	3730'	4 1/2	3730'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ each set.

Shot tubing off @ 3193', Rig up Halliburton pump 55 sks, 60/40 poz, 10% gel, 1/4# floccel per sk, pulled tubing to 1700' ran perforating gun 3 shots to 1750' shot 3 hole pump 33 sks 60/40 poz, 10% gel, 1/4# floccel. Pulled tubing to 900' from surface, pumped 36 sks, cement circulate to surface, pulled tubing, perforate 4 1/2 csg @ 350'. Pump 83 sks cement down 8 5/8 circulated to surface through 4 1/2 csg, pressure 300#.

(If additional description is necessary, use BACK of this form.)

Ostrum  
Name of Plugging Contractor Halliburton Drilling Company License No. 5988  
Address 1102 E. Eight P.O. Box 428 Hays, KS 67601  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HALLWOOD PETROLEUM, INC.

STATE OF COLORADO, COUNTY OF DENVER, ss.

Bruce Hoffman, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bruce Hoffman  
(Address) 4582 S. Ulster St., DENVER, CO 80237

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1993.

M. M. Christian  
Notary Public

My Commission Expires: 9/1/97

RECEIVED  
STATE CORPORATION COMMISSION

NOV 29 1993  
11-29-93  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-4