

2-15-84

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,032--80--60

LEASE NAME Balthazor

WELL NUMBER 9

990 Ft. from N Section Line

2970 Ft. from W Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SEC. 13 TWP. 9S RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 8/9/84

Plugging Commenced 5/14/97

Plugging Completed 5/15/97

LEASE OPERATOR Hallwood Petroleum, Inc.

ADDRESS 4582 S. Ulster St. Parkway, Suite 1700, Denver, CO 80237

PHONE# (303) 850-6257 OPERATORS LICENSE NO. 3613

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/25/97 (date)

by KCC District 4 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation L-KC Depth to Top 3481' Bottom 3643' T.D. 3820'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	328'	8 5/8"	328'	-0-
		-0-	3812'	5 1/2"	3812'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran 30 sx of cmt & spotted over perf, cmtd 270 sx of 60/40 Poz w/10% gel, tag cmt at 470' dwn from suface, 200' of fluid in hole, ran tbg to 460', swabbed fluid out of wellbore, pulled tbg & cut off 8 5/8" & 5 1/2", ran line & tagged cmt in surface pipe 70' from surface, filled surface pipe & 5 1/2" to surface w/redimix, covered location. Well plugged & abandoned 5/15/97.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Energy Services, Inc. License No. 5988

Address P. O. Box 428, Hays, KS 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Nonya K. Durham (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Nonya K. Durham
Nonya K. Durham, Production Reporting Supervisor
(Address) P. O. Box 378111, Denver, CO 80237

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 97



STATE CORPORATION COMMISSION
JUN 9 1997
6-9-97
CONSERVATION DIVISION
Wichita, Kansas

Judy E. Young
Judy E. Young, Notary Public

Commission Expires: 4/19/01