

15-163-20309-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5/25/70
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C - G Drlg. Co. & D. G. Hansen Trust

Complete Address 1107 Union Nat'l Bldg., Wichita, Kansas

Lease Name Thyfault Well No. 3

Location NW SE NW Sec. 8 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3713

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor C & G Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30P Day 23 Month 5 Year 1970

The above well was plugged as follows:

RTD 3713' 8 5/8 csg set at 176' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 5/25/70

INV. NO. 1929-W