

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks \_\_\_\_\_

Location: SE SE SW Sec. 9 Twp. 9 Rge. 20 (E) (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3676

I have this date completed supervision of plugging of:

Lease Name: Whisman Well No. A-3

Operator's Full Name: I. O. Miller

Complete Address: 619 Brown Bldg Wichita, Kansas

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kansas License No. 49

Oil Well \_\_\_\_\_ X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 1 Month 1 Year 61

The above well was plugged as follows:

8 5/8" 245' circulated with cement - 5 1/2" at 3668' with 140 sax cement.  
Filled with sand to 3650', set 4 sax cement with dump bailer, pulled  
1000' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550'  
( 22 sax gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to  
170', displaced 20 sax cement through 5 1/2" at 170', heavy mud to 35', set  
bridge and 10 sax cement to bottom cellar.  
Mudding and cementing by Halliburton Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

**INVOICED**  
DATE 1/26/61  
INV. NO. 2562-u

1/10/61