

15-163-03425-00-00

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1/18/61  
JAN 18 1961  
CONSERVATION DIVISION  
WICHITA, KANSAS

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks

Location: SW NW SE Sec. 9 Twp. 9 Rge. 20 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3671

I have this date completed supervision of plugging of:

Lease Name: Whisman Well No. A-2

Operator's Full Name: I. O. Miller

Complete Address: 619 Brown Bldg Wichita, Kansas

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kansas License No. 49

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2PM Day 4 Month 1 Year 61

The above well was plugged as follows:

8 5/8" 245' circulated with cement. 5 1/2" 3635' with 120 sax cement.

Filled hole with sand to 3650', set 4 sax cement with dump bailer, pulled

2620', 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" (50 sax Gel)

displaced 20 sax cement through 5 1/2" at 500', heavy mud to 170', displaced

20 sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10

sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Edon Petty*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

INVOICED  
DATE 1/26/61  
INV. NO. ~~2563-W~~  
2563-W