

15-163-03427-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

ST
1/18/61
JAN 18 1961
ED
COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rocks _____
Location: NE SE SW Sec. 9 Twp. 9 Rge. 20 (E) (W) _____
Name of Field: _____ Total Depth: 3671

I have this date completed supervision of plugging of:

Lease Name: Whisman Well No. A-1

Operator's Full Name: I. O. Miller

Complete Address: 619 Brown Bldg Wichita, Kansas

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kansas License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 11 Month 1 Year 61
~~60~~

The above well was plugged as follows:

8 5/8" 245' circulated with cement - 5 1/2" 3663' 125 sax cement.

Filled with sand to 3650', set 4 sax cement with dump bailer, pulled

2475' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500'

Ø 50 sax Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to

160', displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: Jewel M. Ogden
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 1/26/61
INV. NO. 2564-W