

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
9-16-69
SEP 16 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Patton Oil Company

Complete Address 322 70 west Bldg., 70 W 6th Ave. Denver, Colo.

Lease Name Sparks Well No. 1

Location SE NE SW Sec. 34 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson

Address Wichita, Ks. License No.

Operation Completed: Hour 11:30A Day 12 Month 9 Year 1969

The above well was plugged as follows:

RTD 3710' 8 5/8 csg set at 216' cwe Cmt. Mat. 50-50 poz cmt 6%
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/16/69
INV. NO. 480-W

Signed: [Signature]
Well Plugging Supervisor