

15-163-20371-00-06

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6/24/71
JUN 24 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company and Woodman-Iannitti,

Complete Address 217 North Water, Wichita, Kansas.

Lease Name George Whisman Well No. D-2

Location NW-NE-SW Sec. 9 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company

Address 617 Union Center Building, Wichita, Ks. License No.

Operation Completed: Hour 9:00 PM Day 20 Month 6 Year 1971

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 100 Sx. cement thru
DP from 925' to 600'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from 245'
to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Nichols
Well Plugging Supervisor

DATE 6/24/71
INV. NO. 3912-W