

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202API Number 15 -163 -20334-00-00 (of this well)

Operator's Full Name Woodman-Iannitti Drilling Co.

Complete Address Box 308, Great Bend, Kansas 67530

Lease Name Whisman Well No. 1

Location S/2 NE SW Sec. 9 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3675'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 4 P Day 14 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 3675' 8 5/8 csg set 202' cwc 150 sx.

5 1/2 csg set 3671' cw 150 sx cem.

5 1/2 csg PBSD 3642' & perf. (3428'-3434')

Set 5 1/2" wood plug at 3400' -poured 25' sd & dumped 4 sx cem W/dump bailer. (3400'-3345')

Cutoff & recovered 2621' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs
hulls -70 sk 50-50 poz 6% -10 sk gel & water -plug & 50 sx 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rico Murray
Well Plugging SupervisorDATE 7/29/76INV. NO. 3538-U