

Form GP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

OCT 22 1963  
10-22-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name A (Bud) Ainsworth

Complete Address: 715 4th Natl Bk Wichita, Kans

Lease Name O' Brien Well No. 1

Location SW NW NE Sec. 34 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3550

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated: wash down

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kans License No. 436

Operation Completed: Hour 3PM Day 13 Month 10 Year 63

The Above well was plugged as follows:

8 5/8" 302' Circulated with cement @ 4 1/2" 3515' with 100 sax cement -  
Perf 3412' - Filled with sand to 3400', set 3 sax cement with dump bailer--  
pulled 2870' 4 1/2" to 600' - circulated hole with heavy gel mud through  
4 1/2" ( 27 sax gel) displaced 20 sax cement through 4 1/2" at 600', heavy mud  
to 250' - displaced 20 sax cement through 4 1/2" at 250' - heavy gel mud  
to 35', set bridge and filled to bottom cellar with cement,

Mudding and cementing by Knight Casing Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edou Letty  
Well Plugging Supervisor

DATE 10/22/63  
INV. NO. 4933-U