

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 34 TWP. 9 RGE. 19 W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Webster

Operator W. L. Hartman Address Wichita,

Field _____ County Rooks

Total Depth 3650 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" casing at 162' circulated with cement - 5 1/2 3640'
Lans Wells plugs and cement 3650' to 3290, Perforated
at 3280' - Heavy mud to 3270' - rock bridge and 5 sax cement.
Heavy mud to 165' wood plug, rock and 15 sax cement, heavy
mud to 30', wood plug and 10 sax cement.

RECEIVED
Conservation Div. District Conservation Agent
[Signature]

Date 3 - 1 - 49

PLUGGING
FILE SEC 34 T 9 R 19
BOOK PAGE 25 LINE 30
CORPORATION
COMMISSION
KANSAS