



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CNE NW SE

SEC. 7 TWP. 9 RGE. 20

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Emile Desmarteau

Operator Skelly Oil Co Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3800 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 284' circulated with cement.

25 sax cement pumped through drill pipe on bottom -

filled with heavy rotary mud to 325', set wood plug and

25 sax cement through drill pipe - heavy mud to 60' set wood

plug ~~at~~ at 60' filled to surface with cement.

Cementing by Halliburton Co.

PLUGGING  
7.9.50  
133 8w

District Conservation Agent

Date 1-11-50

1/11/50