

KANSAS

2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1972
6-14-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling & Jet Drilling Co.

Complete Address Suite 905 Century Plaza, Wichita, Kansas

Lease Name Bouchey Well No. 1

Location SE NW SW Sec. 30 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3765'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 6:20 P Day 12 Month 6 Year 1972

The above well was plugged as follows:

RTD 3765' 8 5/8 csg set at 225' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 875' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 250' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Messing
Well Plugging Supervisor

INVOICED
DATE 6-14-72
INV. NO. 5874-W