

KANSAS

Form CP-3  
Rev. 6-26-62

*14*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAY 31 1967  
5-31-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company

Complete Address: Victoria, Kansas

Lease Name Sparks Well No. 1

Location NE SW SE Sec. 33 Twp. 9 Rge. 19 (E) (W) X

County Rooks Total Depth ~~3600~~ 3723

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 1-P Day 29 Month 5 Year 1967

The Above well was plugged as follows:

RTD ~~3600~~ <sup>3723</sup> 8 5/8 csg set at 164' cwc 125 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 20 sc cem. thru drill pipe. Heavy mud to 160' set cementing plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 5/31/67

INV. NO. 5307-W