

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasJAN 28 1964
1-28-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Co

Complete Address: Box 649 Mc Cook, Neb

Lease Name Casey Well No. 3

Location NW NE SW Sec. 33 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3744

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kans License No. 436

Operation Completed: Hour 12 Noon Day 25 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 296' circulated with cement - 5 1/2" 3735' with 175 sax cement

Sanded back to 3720' set 4 sax cement with dump bailer - pulled

2845' 5 1/2" to 550' - circulated hole with 56 sax mud - displaced

20 sax cement through 5 1/2" at 550', heavy mud to 250', displaced 20 sax

cement through 5 1/2" - heavy mud to 35', set bridge and 10 sax cement

to bottom cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Kelly
Well Plugging SupervisorDATE 1/28/64INV. NO. 8542-W