

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 21-28
LOCATION SW SW SE
SEC. 33 TWP. 9 RGE. 19

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Sparks
Operator W. L. Hartman Address Wichita, Kans
Field _____ County Rooks
Total Depth 3745 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 191' circulated with cement - 5 1/2" at 3745' with
25 sax cement behind. Perf at 3720'.

Filled with sand to 3710' set 4 sax cement with dump bailer,
pulled 2230' 5 1/2", filled with mud to 190', set rock bridge
and 15 sax cement, mud to 35', set rock and 10 sax cement
to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1952
6-26-52
CONSERVATION DIVISION
Wichita, Kansas

Edwin J. [Signature]
District Conservation Agent

Date 6-26-52