

KANSAS

AP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1973
2-16-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas 67202
Lease Name Hamel Well No. 3
Location SW SE SW Sec. 33 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3746'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas License No. 399
Operation Completed: Hour 12 N Day 15 Month 2 Year 1973

The above well was plugged as follows:

Total Depth 3746' 8 5/8 csg set at 176' cwc 100 sk.
5 1/2 csg set at 3740' cw 125 sk.
Filled 5 1/2 csg W/sd (3700-3746) Dumped 5 sk cmt W/dump bailer. (3665-3700)
Dakato squeezed -cutoff and recovered 728' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug
and pumped 100 sk "Halib-Light" cmt by HOWCO. PP 500 lbs. SIP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 2/16/73
INV. NO. 6989-11