

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1973
2-16-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas 67202
Lease Name Hamel Well No. 2
Location NE SW SW Sec. 33 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3741'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10:30 A Day 15 Month 2 Year 1973

The above well was plugged as follows:

Total Depth 3741' 8 5/8 csg set at 176' cwc 125 sk.

5 1/2 csg set at 3738 1/2 cw 125 sk cmt.

5 1/2 csg PBDT 3634' with perf. (3413-3417)

Dakato squeezed.

Set 5 1/2 wood plug at 3400' -poured 10' sd -dumped 5 sk cmt W/dump bailer. (3350-3400)

Cutoff and recovered 637' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug
and pumped 100 sk "Halib-Light" cmt by HOWCO. PP 450 lbs. SIP 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leslie Massey
Well Plugging Supervisor

DATE 2/16/73
INV. NO. 6988-4