

KANSAS

Yp
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
JAN 30 1967
1-30-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Phillips Petroleum Company

Complete Address: Box 287 Great Bend, Kansas

Lease Name Nech Well No. 2

Location NE NE SE Sec. 15 Twp. 9 Rge. 19 (E) (W) X

County Rooks Total Depth 3501'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight casing pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11 A Day 26 Month 1 Year 1966

The Above well was plugged as follows:

Total Depth 3501' 8 5/8 csg set at 1483' cwc.

5 1/2 csg set at 3501' cw 100 sc cement.

Perf. 3496' Sand back to 3480' and dumped 5 sc cement with dump bailer.

Recov. 2625' of 5 1/2 csg.

Set plug at 420' and rock to 400' Filled with 6 yds. readymix cement 400' to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *L. J. Massey*
Well Plugging Supervisor

INVOICED
DATE 1/30/67
INV. NO. 4689-W