

KANSAS  
STATE CORPORATION COMMISSION

*R*

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 128-20 County: Rooks

Location: SW SW NW Sec. 33 Twp. 9 Rge. 19 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3766

I have this date completed supervision of plugging of:

Lease Name: Richardson Well No. 1

Operator's Full Name: Sierra Pet Co

Complete Address: 208 Pet Bldg Wichita, Kans

Plugging Contractor: South West Casing Pulling

Address: Great Bend, Kans License No. 399

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 21 Month 9 Year 58

The above well was plugged as follows:

8 5/8" 151' circulated with cement - 5 1/2" 3762' with 60 sax cement behind.  
Pulled 1020' 5 1/2" to 700', circulated hole with heavy mud through 5 1/2"  
(55 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud  
to 140', displaced 20 sax cement through 5 1/2", heavy mud to 35', set  
rock bridge and 10 sax cement to 0'.  
Mudding and cementing by Sun Cementing Co.

Signed: *Edson Perry*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

RECEIVED  
STATE CORP COM  
SEP 24  
9-26-58  
PLUGGING  
FILE SEC. 33 T. 9 R. 19W  
BOOK PAGE 128 LINE 20