

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

2-13-62  
DIVISION  
a, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks \_\_\_\_\_

Location: SW NE SW Sec. 33 Twp. 9 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 19

Name of Field: \_\_\_\_\_ Total Depth: 3731

I have this date completed supervision of plugging of:

Lease Name: Casey Well No. 2

Operator's Full Name: Skelly Oil Co

Complete Address: 212 Wolcott Bldg Hutchinson, Kansas

Plugging Contractor Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour w 3PM Day 10 Month 2 Year 62

The above well was plugged as follows:

8 5/8" 323' circulated with cement - 5 1/2" 3731 with 150 sax cement - tem p  
survey on 5 1/2" 2850' - perf 3192' - PB and sand to 3180', set 5 sax cement  
at 3180' with dump bailer - pulled 2811' 5 1/2" to 550', circulated hole with  
heavy mud through 5 1/2" at 550' ( 27 sax Gel), displaced 20 sax cement through  
5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180',  
heavy mud to 35', set bridge and cement to bottom cellar.  
Mudding and cementing by Sun Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 2/14/62  
INV. NO. 4541-W