

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

JAN - 3 1979
1-3-79
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

API Number 15 - 163-00131-00-00

Operator's Full Name Theodore Gore
Complete Address Suite 1750, 125 North Market, Wichita, Ks. 67202
Lease Name Nech Well No. 1
Location SE NE NE Sec. 15 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3503 1/2
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Kelso Casing Pulling
Address Box 176, Chase, Kansas 67524 License No. 683
Operation Completed: Hour 2:45 P Day 29 Month 12 Year 1978

The above well was plugged as follows:

Total Depth 3503 1/2 8 5/8 csg set 174' cwc 125 sk.
5 1/2 csg set 3497 1/2 cw 100 sk cem. Top perf. (3239')
Filled 5 1/2 csg W/sd to 3200' -dumped 4 sk cem W/dump bailer.
Cutoff & recovered 835' of 5 1/2 csg.
Allied Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water, released cementing plug & capped with 125 sk 50-50 poz 6% & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-3-79

INV. NO. 8882-W

Signed: [Signature]
Well Plugging Supervisor