

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163 - 02242 - 00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Co.

Complete Address Box 287 St. Bend, Ks. 67530

Lease Name Neck Well No. 4

Location NE-NW-SE Sec. 15 Twp. 9 Rge. 19 (East) (West)

County Rooks Total Depth 3509'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Hallikuntan Cementing Co.

Address Hays, Kansas 67601 License No. _____

Operation Completed: Hour: 11:00 AM Day: 20 Month: 10 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 207' w/200 cv - 5 1/2" @ 3506 w/150 cv -
2nd stage @ any w/375 cv cont. to surface
Ordered 175 cv. 5%oz. 67 gel - 4 hulls - 5 1/2" plug
supplied 5 1/2" 10 cnt -> 15 cnt. 4 hull -> 16 gel -> Rel plug
135 cnt: Hook-up to 8 5/8" - pressured up:
5 1/2" pressure 1000# P.S.I. 8 5/8" - 200# P.S.I. -

Amount of Surface Casing: 207'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis J. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
10-26-82
OCT 26 1982

Signed: _____
Conservation Division Agent
Wichita, Kansas

INVOICED
DATE 11-5-82
INV. NO. 1500-W