

TIGHT ORIGINAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32309
Name: Presco Western, LLC
Address: 5480 Valmont, Ste. 350
City/State/Zip: Boulder, CO 80301
Purchaser: Plains Marketing LP - oil OneOK - gas
Operator Contact Person: Leonard Witkowski
Phone: (303) 444-8881
Contractor: Name: Murfin
License: 30606
Wellsite Geologist: None - Boulder office

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

10/07/2005 10/17/2005 10/28/2005
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 081-21619-00-00
County: Haskell
C SE SE SE Sec. 2 Twp. 28 S. R. 33 East West
330 feet from S N (circle one) Line of Section
330 feet from E W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Cox Well #: 6-P2-28-33
Field Name: Hugoton

Producing Formation: Morrow/St. Louis
Elevation: Ground: 2970.48 Kelly Bushing: 2981.48
Total Depth: 5647 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 1709 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content 8000 ppm Fluid volume 1800 bbls
Dewatering method used Air Evaporation

Location of fluid disposal if hauled offsite:

Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. APR 05 2006 East West
County: _____ Docket No.: _____
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KS

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Leonard Witkowski


Title: Regulatory Specialist Date: 04/04/2006

Subscribed and sworn to before me this 4th day of _____

2006

Notary Public: Roberta Jo Lyon

Date Commission Expires: 1/26/2008



KCC Office Use ONLY

- Letter of Confidentiality Received
- If Denied, Yes Date: _____
- Wireline Log Received
- Geologist Report Received
- UIC Distribution

TIGHT

Side Two

Operator Name: Presco Western, LLC Lease Name: Cox Well #: 6-P2-28-33
Sec. 2 Twp. 28 S. R. 33 East West County: Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken [] Yes [x] No
Samples Sent to Geological Survey [] Yes [x] No
Cores Taken [] Yes [x] No
Electric Log Run [x] Yes [] No

List All E. Logs Run:

Cement Bond log; Compensated neutron/SSD log; Dual Induction log

Table with 3 columns: Name, Top, Datum. Rows include Lansing (4214, -1233), Kansas City (4630, -1649), Marmaton (4792, -1811), Morrow (5185, -2204), Ste. Gen (5460, -2479), St. Louis (5510, -2529).

CASING RECORD table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Rows for Surface and Production.

ADDITIONAL CEMENTING / SQUEEZE RECORD table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives. Includes a 'RECEIVED' stamp from the Kansas Corporation Commission dated APR 05 2006.

PERFORATION RECORD - Bridge Plugs Set/Type table with columns: Shots Per Foot, Specify Footage of Each Interval Perforated, Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used), Depth. Rows for 5247-5264 and 5368-5373.

TUBING RECORD table with columns: Size, Set At, Packer At, Liner Run. Includes production data: Date of First Resumerd Production (1/12/2006), Producing Method (Flowing), Estimated Production (Oil 6 Bbls, Gas 57 Mcf, Water 1 Bbls, Gas-Oil Ratio 9500, Gravity 37.5).

Disposition of Gas METHOD OF COMPLETION Production Interval
[] Vented [x] Sold [] Used on Lease [] Open Hole [x] Perf. [] Dually Comp. [] Commingled
(If vented, Submit ACO-18.) [] Other (Specify)

ALLIED CEMENTING CO., INC. 21910

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Ogkley

DATE <u>10-8-05</u>	SEC. <u>2</u>	TWP. <u>28s</u>	RANGE <u>33w</u>	CALLED OUT	ON LOCATION <u>7:15 PM</u>	JOB START <u>2:00 AM</u>	JOB FINISH <u>3:00 AM</u>
LEASE <u>Cox</u>	WELL# <u>6-P²-26-33</u>	LOCATION <u>Sublette - 11 N 1/4 W N/S</u>			COUNTY <u>Haskell</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Murfin Drig Rig 21

TYPE OF JOB Surface

HOLE SIZE 12 1/4 T.D. 1756

CASING SIZE 8 7/8 DEPTH 1756-48'

TUBING SIZE DEPTH 1716'

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 40.48'

CEMENT LEFT IN CSG. 40.48'

PERFS.

DISPLACEMENT 1084 Bbls

EQUIPMENT

OWNER Same

CEMENT

AMOUNT ORDERED 150 sks com 3% cc

575 sks Lite 3% cc w/ 4" Flo Seal

COMMON	<u>150 sks</u>	@ <u>10.00</u>	<u>1500.00</u>
POZMIX		@	
GEL		@	
CHLORIDE	<u>24 sks</u>	@ <u>38.00</u>	<u>912.00</u>
ASC		@	
Liteweight	<u>575 sks</u>	@ <u>9.30</u>	<u>5347.50</u>
		@	
Flo Seal	<u>144 #</u>	@ <u>1.70</u>	<u>244.80</u>
		@	
		@	
		@	
		@	
HANDLING	<u>778 sks</u>	@ <u>1.60</u>	<u>1244.80</u>
MILEAGE	<u>64 / sk mile</u>		<u>210.60</u>
TOTAL			<u>11349.70</u>

PUMP TRUCK CEMENTER Dean

373-281 HELPER Andrew

BULK TRUCK

347 DRIVER Lennie

BULK TRUCK

386 DRIVER Kelly

REMARKS:

Ran 42 Joints 8 7/8 Pipe.
Cemented w/ 575 sks Lite 3% cc w/ 4"
Flo Seal followed w/ 150 sks com 3% cc.
Disp Plug. Cement did Circulate.
Plug Did Not Land.
Plant Held
Thank you

SERVICE

DEPTH OF JOB

PUMP TRUCK CHARGE 1320.00

EXTRA FOOTAGE @

MILEAGE 45 miles @ 5.00 225.00

MANIFOLD @

RECEIVED @

KANSAS CORPORATION COMMISSION @

TOTAL 1545.00

CHARGE TO: Presco Western

STREET _____

CITY _____ STATE _____ ZIP _____

RECEIVED
KANSAS CORPORATION COMMISSION

APR 05 2006

CONSERVATION DIVISION
WICHITA, KS PLUG & FLOAT EQUIPMENT

Guide shoe	@	<u>235.00</u>
APU Insert	@	<u>325.00</u>
4 - Centralizers	@ <u>55.00</u>	<u>220.00</u>
1 - Basket	@	<u>180.00</u>
8 7/8 Rubber Plug	@	<u>100.00</u>
TOTAL		<u>1060.00</u>

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Rodny Gonzalez

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

Rodny Gonzalez
PRINTED NAME

ALLIED CEMENTING CO., INC. 19940

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>10-16-05</u>	SEC. <u>2</u>	TWP. <u>28S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>9:15 PM</u>	JOB START <u>3:30 AM</u>	JOB FINISH <u>4:30 AM</u>
LEASE <u>COX</u>	WELL# <u>6-P2</u>	LOCATION <u>Sublette 11N-14W-N2W</u>			COUNTY <u>HASKELL</u>	STATE <u>Ks</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

RECEIVED
KANSAS CORPORATION COMMISSION
APR 05 2006
CONSERVATION DIVISION
WICHITA, KS

CONTRACTOR MURFIN DRILL RIG #21
 TYPE OF JOB Production string
 HOLE SIZE 7 7/8" T.D. 5647'
 CASING SIZE 5 1/2" DEPTH 5640'
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL PORT COLLAR DEPTH 3170'
 PRES. MAX 1800PSI MINIMUM 200PSI
 MEAS. LINE SHOE JOINT 21.68'
 CEMENT LEFT IN CSG. 21.68'
 PERFS.
 DISPLACEMENT 133 3/4 BBL

OWNER SAME
 CEMENT
 AMOUNT ORDERED
280 SKS ASC 10% SALT 28GEL 20F1% FI-160
500 GAL WFR-2
 COMMON @
 POZMIX @
 GEL 5 SKS. @ 14.00 70.00
 CHLORIDE @
 ASC 280 SKS @ 11.65 3262.00
 @
SALT 28 SKS @ 15.25 441.00
FI-160 132 @ 8.20 1148.40
 @
WFR-2 500 GAL @ 1.00 500.00
 @
 @
 @
 HANDLING 320 SKS @ 1.60 529.60
 MILEAGE 64 PER SK/ MILE 893.76
 TOTAL 6844.76

EQUIPMENT

PUMP TRUCK CEMENTER TERRY
 # 191 HELPER WAYNE
 BULK TRUCK
 # 386 DRIVER LOWME
 BULK TRUCK
 # DRIVER

REMARKS:

MIX 500 GAL WFR-2, MIX 10SKS CEMENT MIDGE HOPE, MIX 15 SKS CEMENT RAY HOPE, MIX 255 SKS ASC 10% GEL 28GEL 20F1% FI-160 WASH TRUCK & LINES, DISPLACE 133 3/4 BBL WATER, PLUG LANDED AT 1800PSI, FLOAT HELD.

THANK YOU

CHARGE TO: PRESCO-WESTERN
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB 5640'
 PUMP TRUCK CHARGE 1320.00
 EXTRA FOOTAGE @
 MILEAGE 45 MI @ 5.00 225.00
 MANIFOLD @
 @
 @
 TOTAL 1545.00

5 1/2" PLUG & FLOAT EQUIPMENT

1- Guide shoe 160.00
1- AFU INSERT @ 235.00
7- CENTRALIZERS @ 50.00 350.00
1- BASKET @ 140.00
1- PORT COLLAR @ 1750.00
1- RUBBER PLUG @ 60.00
 TOTAL 2695.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzales Rodney Gonzales
 PRINTED NAME

ALLIED CEMENTING CO., INC. 19672

Federal Tax I.D.# 48-0727860

EMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley

DATE <u>10/2/05</u>	SEC. <u>2</u>	TWP. <u>29s</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>11:15 AM</u>	JOB START <u>12:10 PM</u>	JOB FINISH <u>1:30 PM</u>
LEASE <u>Cox</u>		WELL # <u>6-P2</u>		LOCATION <u>Sublette 11N 14W N/S</u>		COUNTY <u>Haskell</u>	STATE <u>KS</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR Eldridge Well Service
 TYPE OF JOB Cmt Port Collar
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 15.5" DEPTH _____
 TUBING SIZE 2 7/8 DEPTH 3116
 DRILL PIPE _____ DEPTH _____
 TOOL Port Collar DEPTH 3116
 PRES. MAX 1500 MINIMUM 100
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT 18 BBL

OWNER SAMC
 CEMENT AMOUNT ORDERED
300sk Lite + K#Flo-Seal

EQUIPMENT
 PUMP TRUCK CEMENTER Max
 # 373-281 HELPER Jerrad
 BULK TRUCK
 # 386 DRIVER Lannie
 BULK TRUCK
 # _____ DRIVER _____

COMMON	@	_____	_____
POZMIX	@	_____	_____
GEL	@	_____	_____
CHLORIDE	@	_____	_____
ASC	@	_____	_____
<u>Litemight 300sk</u>	@	<u>8.90</u>	<u>2640.00</u>
<u>Flo-Seal 75#</u>	@	<u>1.70</u>	<u>127.50</u>
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
HANDLING <u>324</u>	@	<u>1.60</u>	<u>518.40</u>
MILEAGE <u>60/sk/mi</u>			<u>874.80</u>
TOTAL			<u>4160.70</u>

REMARKS:

Test Csg. to 1500 PSI open tool
Establish Rate Mix 300sk Cmt
Displace 17 1/2 BBL close tool
Test Csg. to 1500 PSI hold
Reverse Hole Clean
Cement did Circulate

SERVICE

DEPTH OF JOB	<u>3116</u>		
PUMP TRUCK CHARGE			<u>795.00</u>
EXTRA FOOTAGE	@	_____	_____
MILEAGE <u>45 mi</u>	@	<u>5.00</u>	<u>225.00</u>
MANIFOLD	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
TOTAL			<u>1010.00</u>

CHARGE TO: Presco Western
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

RECEIVED
 KANSAS CORPORATION COMMISSION
 @ **APR 05 2006**
 @
 CONSERVATION DIVISION
 WICHITA, KS

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzalez

Rodney Gonzalez
 PRINTED NAME